Conversion of Old GCTs to the WASSTRIP® Process, SWRP

Project Number: 15-120-3P

Service Area: Stickney

Location: Stickney WRP

Engineering Consultant: In-house design

General Contractor: To be determined

Estimated Construction Cost: \$15,000,000

Contract Award Date: April 2016*

Substantial Completion Date: April 2018*



<u>Project Description</u>: The remaining old gravity concentration tanks will be converted to the Waste Activated Sludge Stripping to Remove Internal Phosphorus (WASSTRIP®) process to aid in the release of phosphorus which will be recovered from the pre-digestion centrate by the existing Ostara process.

<u>Project Justification</u>: The WASSTRIP® process will increase the quantity of phosphorus that will be recovered by the Ostara facility. This enhances the District's strategic plan toward sustainability and resource recovery. Additional benefits of this process will be the reduction of struvite formation in the digesters and post centrate piping as well as improving the dewaterability of our biosolids. The fermentation of primary sludge will create additional volatile fatty acids necessary for a more stable operation of the enhanced biological phosphorus removal treatment process.

Project Status: This project is being designed.

^{*}Information shown is estimated.