

Streambank Stabilization Project on Oak Lawn Creek

Project Number: 10-237-3F

Service Area: Calumet

Location: Oak Lawn, IL

Engineering Consultant: MWH Americas, Inc.

General Contractor: To be determined

Estimated Construction Cost: \$4,500,000

Contract Award Date: September 15, 2016*

Substantial Completion Date: September 15, 2018*



Project Description: Stabilization of approximately 1,200 linear feet of Oak Lawn Creek, from Central Avenue to Massasoit Avenue in Oak Lawn, using soldier piles and precast concrete panels. Trees and other plantings will be installed upon completion of the wall.

Project Justification: Safety/Regulatory. The creek banks have deteriorated due to hydraulic erosion and slope failures, thus potentially compromising the slopes and impacting residential structures that are in the vicinity.

Project Status: Design is complete. Permits have been received.

This project is funded under the Capital Improvements Bond Fund. See Section V Capital Budget for additional information.

*Information shown is estimated.