

Restoration of Egan WRP Permeable Paver Parking Lot

Project Number	25-721-21
Service Area	North
Location	Egan WRP
Engineering Consultant	In-house design
Engineering Contractor	To be determined
Estimated Construction Cost	\$150,000
Contract Award Date	September 2025
Substantial Completion Date	December 2025
Project Description	Restore the permeable pavement parking lot at the Egan WRP, which includes replacing stone joint material, cracked or damaged pavers, and leveling as needed.
Project Justification	The permeable pavement parking lot at the Egan WRP naturally diverts stormwater and includes an underdrain system to help alleviate flooding while safeguarding our rivers and natural water resources from pollutants during large rain events. Rehabilitation, including the releveling and replacement, as needed, of the pavers that top this system is required to ensure the drainage system continues to work effectively.
Project Status	Planning

