

## Kirie - Egan Solids Pipeline Rehabilitation Section No. 1, NSA

<b>Project Number</b>	23-416-2S
<b>Service Area</b>	North
<b>Location</b>	Egan WRP
<b>Engineering Consultant</b>	In-house design
<b>Engineering Contractor</b>	To be determined
<b>Estimated Construction Cost</b>	\$4,800,000
<b>Contract Award Date</b>	December 2024
<b>Substantial Completion Date</b>	March 2026
<b>Project Description</b>	This project will consist of the rehabilitation of 2,705 feet of 18" sewer by Cured-In-Place Pipe (CIPP) lining process between stations 0+00 and 27+05. Four (4) manholes will be rehabilitated with spray-on epoxy products and by carbon fiber reinforced polymer lining system.
<b>Project Justification</b>	There have been a total of four breaks along the existing 18-inch solids pipeline between stations 0+00 and 27+05 as reported by the Maintenance & Operations Department. The subject contract will rehabilitate the existing pipeline between these stations to address the aforementioned critical areas.
<b>Project Status</b>	Design

