

Odor Control Facilities at Sludge Concentration, Southwest Coarse Screen, Overhead Weir, and Post-Centrifuge Building, SWRP

Project Number: 17-134-3M

Service Area: Stickney

Location: Stickney WRP

Engineering Consultant: In-house design

General Contractor: To be determined

Estimated Construction Cost: \$15,000,000

Contract Award Date: December 2018*

Substantial Completion Date: September 2020*



Project Description: Three biofilter facilities will be constructed, one for sludge concentration and overhead weir, one for the southwest coarse screen, and one for the post-centrifuge building. The facilities will include new biofilters, Heating, Ventilation, and Air Conditioning equipment, ductwork, and other ancillary equipment.

Project Justification: This project will reduce the odor emissions that affect the District's neighbors and staff. The plant is located near a residential neighborhood.

Project Status: The project is being designed.

*Information shown is estimated.